

**Annexure-1****Name of Work: Toilet repairing work at dahej sez part-2**

<b>Sr. No.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Submitted Rate (Rs.) in Figure</b>	<b>Submitted Rate (Rs.) in Word</b>	<b>Total Amount</b>
1	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. ( R.C.C Work )	1.35	Cmt			
2	Excavation for foundation for depth upto 3. 0 M including sorting out and stacking of useful material and disposing of the excavated stuff as directed by EIC.	3.38	Cmt			
3	Filling in foundation and plinth with brickbats. Charra in layer of 20 cm.thickness including watering remming and consolidation etc.completed.	2.03	Cmt			
4	filling in plinth with sand under floors including watering, raming, consolidating & drassing etc.comp	3.38	Cmt			
5	Providing and laying vitrified Tiles fooling 8mm thick over 20mm (average) base of cement mortar 1:6 liad and jointed with grey cement slurry including rubbing and polishing & skirting etc.complete	6.75	Sq.mt			

Name of Work: Toilet repairing work at dahej sez part-2						
Sr. No.	Particulars	Qty.	Unit	Submitted Rate (Rs.) in Figure	Submitted Rate (Rs.) in Word	Total Amount
6	P & L Brickwork using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:6 (1- Cement : 6- fine sand) as approve by DSL	0.66	Cmt			
7	P/L ordinary cement concrete 1:3:6 (1 Cement :3 coarse sand : 6 graded stone aggregates 20mm nominal size) and finishing smooth with curing etc complete incl.including cost of form work but excluding cost of reinforcement for RCC work for Slab etc.comp.	1.01	Cmt			
8	Availabel Paver block fixing (as per site location ) etc comp as directed by DSL.	6.00	Sq.mt			
9	Green marble for Jambs-sill-thresholds,Supplying,fixing and intaling of Green marble(15-18mm thick) for Door/window jambs,sills,thresholds etc in sizes veyring from 100mm to 230mm width.rate to including for cutting,polishing,edge moulding,joining with adhesives, white cement, wastages of any etc at any level.Measurement shall be on the basis of net area of laid.	1.50	Sq.mt			

Name of Work: Toilet repairing work at dahej sez part-2						
Sr. No.	Particulars	Qty.	Unit	Submitted Rate (Rs.) in Figure	Submitted Rate (Rs.) in Word	Total Amount
10	P/F PVC pipe 6 kg/cm2 of pipe Supreme / finolex or equivalent quality all fitting work.etc completed					
	100 MM dia Pipe 4 kg/cm2	15.00	Rmt			
	75 mm dia Pipe	10.00	Rmt			
	100mm dia coupling	3.00	Nos.			
	75 mm dia coupling	3.00	Nos.			
	100mm dia elbow	3.00	Nos.			
	75mm dia elbow	3.00	Nos.			
11	Misc.Work ( Basine Wash Pipe , 2" CPVC Pipe,Coupling,2" Valve etc.completed.	1.00	Lum-sump			
<b>Total Amount</b>						

Tender Amount: Figure:  
Word:

---



---

**Sign and Seal of authority**

**Note :- Please Visit the site and submit the offer**