

**Name of work: - Repairing / Reconstruction of Compound wall work at Dahej SEZ Area**

For above subject work, invite offer from Pre-qualified contractors.

It is requested to visit the site in consultation with following officials of DSL.

1. Chirag Limachiya (Site Engineer) Mo.9714033995
2. Bhavin Pancholi (Site Engineer) Mo.8128947892

Please submit the offer in seal cover only after verification of work at site.

Time for site visit:- 2.30 P.M. on date 19.07.2021

**Subject mention on seal cover as under.**

**Name of work: - Repairing / Reconstruction of Compound wall work at Dahej SEZ Area**

**Address: - Office of Dahej SEZ Ltd.**

**Dahej SEZ Part-1,**

**At & Po:- Dahej,**

**Ta :- Vagra**

**Dist:- Bharuch**

**Last date of submission on or before 5:00 PM on Date. 26.07.2021**

**Note:- 1) Only Pre-qualified contractor of Dahej SEZ Ltd. Is eligible to quote / submit**

**2) Price bid- Agency has to quote the rate including all taxes but without (GST) as per SEZ Act & Rule and invoice is to be raised under GST Act and mentioned "supply to SEZ under LUT/Bond without payment of GST".**

Name of work :- Repairing / Reconstruction of Compound wall work at Dahej SEZ Area -2021						
Sr. No.	Description	Unit	Qty	Submitted rate	Submitted rate in Words(Rs.)	Total Amount (Rs.)
1	Providing and laying M-200 with curing etc. complete including the cost of formwork but excluding the cost of reinforcement for RCC work.	CMT	8			
2	Providing and laying rulled pointing on hollow block masonry with cement mortar 1:4 curing etc complete.	SQ.MT	125.00			
3	Providing ISI MarkTMT bar FE-415 reinforcement for RCC. work including bending, binding, and placing in position Comp.	KG	398.13			
4	Providing and laying cement concrete 1:3:6 (1-cement : 3- coarse sand : 6 - hand broken stone aggregates 40 mm nominal size ) and curing complete including cost of formwork in foundation and plinth	CMT	1.50			
5	Boring holes of 250mm dia 3.5 mt deep including under reaming inside the bore hole in ordinary soil & disposal of the surplus excavated soil as directed within a lead of 50mt including placing the reinforcement inside bore and casting the pile with cc 1:1.5:3 concrete including etc comp.Detail of Steel Ring 8mm dia @150c/c. Vertical Bar 12mm dia 4Nos. ( As per Drawing ) (RATE INCLUDING CONCRETE & STEEL)	No	9.00			
6	Excavation for foundation for depth upto 3. 0 M including sorting out and stacking of useful material and disposing of the excavated stuff as directed by EIC.	CMT	17.50			
7	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) R.C.C / Masonry etc. As Per Site Condition.	CMT	11.13			

8	Providing And Laying broken glass in RCC Copping at top of C.Wall	Rmt	25.00			
9	Providing and Rubble Pitching including hand packing and filling material with quarry spalls behind abutment and between tons as directed and including labour charge	CMT	6.00			
10	Filling Available excavated earth in plinth / side of foundation etc. in layer not exceeding 20 cm. in depth consolidating each disposing layer by ramming and watering.	CMT	6.00			
11	Brick work using common burnt clay building bricks having crushing strength not less than 35kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:5 (1 Cement : 5 -fine sand)(A)Modular (up to 10 ton)	CMT	16.10			
12	Providing 15 mm thick cement plaster in single coat on rough (Similar) side of single or half brick walls for interior plastering upto floor two level and finished even and smooth in (i) cement mortar 1:3(1-cement : 3-sand)	SQ.MT	170.00			
						<b>Total =</b>

Tender Amount Figure :

Word :

Sign & Stemp of Authority

**Not 1) Please visit the site and submit the offer /Rate**

**2) DSL reserve the right to increase / decrease scope of work / item/ Quantity as decided by DSL Authority.**

Place :-

Date :-

# SEZ PART - II

PRODUCED BY AN AUTODESK STUDENT VERSION

PRODUCED BY AN AUTODESK STUDENT VERSION



25mt  
 (Emergency Basis)

R.NO.11

2mt  
 15mt  
 45mt  
 R.NO.12

c. wall Repairing  
 Work Approximate :- 87 R.mt