

Name of work: - Toilet repairing work at Dahej SEZ part-2

For above subject work, re-invite offer from Pre-qualified contractors.

It is requested to visit the site in consultation with following officials of DSL.

1. Chirag Limabachiya (Site Engineer) Mo. 9714033995
2. Parth N Patel (Jr. site Engineer) Mo. -8154938449

Please submit the Offer in seal cover only after verification of work at site.

Subject mention on seal cover as under.

Name of work: - Toilet repairing work at Dahej SEZ part-2

Address: - Office of Dahej SEZ Ltd.

Dahej SEZ Part-1,

At & Po: - Dahej,

Ta: - Vagra,

Di:-Bharuch.

Last Date of submission on or before:-17.06.2019

Note: Only Pre-Qualified contractor of Dahej SEZ Ltd. is eligible to quote / submit the offer.

Name Of Work :- Toilet repairing work at dahej sez part-2

Price-bid

Sr. No.	Description	Unit	Qty	Submitted Rate (Rs.)	Submitted Rate in words (Rs.)	Total Amount (Rs.)
1	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (R.C.C Work)	Cmt	1.35			
2	Excavation for foundation for depth upto 3.0 M including sorting out and stacking of useful material and disposing of the excavated stuff as directed by EIC.	Cmt	3.38			
3	Filling in foundation and plinth with brickbats. Charra in layer of 20 cm.thickness including watering remming and consolidation etc.completed.	Cmt	2.03			
4	filling in plinth with sand under floors including watering, raming, consolidating & drassing etc.comp	Cmt	3.38			
5	Providing and laying vitrified Tiles fooling 8mm thick over 20mm (average) base of cement mortar 1:6 liad and jointed with grey cement slurry including rubbing and polishing & skirting etc.complete	Sq.mt	6.75			
6	P & L Brickwork using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:6 (1- Cement : 6- fine sand)	Cmt	0.66			
7	P/L ordinary cement concrete 1:3:6 (1 Cement :3 coarse sand : 6 graded stone aggregates 20mm nominal size) and finishing smooth with curing etc complete incl.including cost of form work but excluding cost of reinforcement for RCC work for Slab etc.comp.	Cmt	1.01			
8	Availabel Paver block fixing (as per site location) etc comp as directed by DSL.	Sq.mt	6.00			

Name Of Work :- Toilet repairing work at dahej sez part-2

Price-bid

Sr. No.	Description	Unit	Qty	Sumitted Rate (Rs.)	Submitted Rate in words (Rs.)	Total Amount (Rs.)
9	Green marble for Jambs-sill-thresholds,Supplying,fixing and intaling of Green marble(15-18mm thick) for Door/window jambs,sills,thresholds etc in sizes varying from 100mm to 230mm width.rate to including for cutting,polishing,edge moulding,joining with adhesives, white cement, wastages of any etc at any level.Measurement shall be on the basis of net area of laid.	Sq.mt	1.50			
10	P/F PVC pipe 6 kg/cm2 of pipe Supreme / finolex or equivalent quality all fitting work.etc completed					
	100 MM dia Pipe 4 kg/cm2	Rmt	15.00			
	75 mm dia Pipe	Rmt	10.00			
	100mm dia coupling	Nos.	3.00			
	75 mm dia coupling	Nos.	3.00			
	100mm dia elbow	Nos.	3.00			
	75mm dia elbow	Nos.	3.00			
11	Misc.Work (Basine Wash Pipe , 2" CPVC Pipe,Coupling,2" Valve etc.completed.	Lum- sump	1.00			
			Total =			

Tender Amount :- Figure:-

Word:-

Sign & Seal of Agency