

Name of work: -Repairing of Toilet Block (Stair case side LHS) in Adm.Bldg. At Dahej SEZ part-1

For above subject work, invite offer from Pre-qualified contractors.

It is requested to visit the site in consultation with following officials of DSL.

1.Chirag Limachiya (Site Engineer) Mo.9714033995

2. BhavinPancholi (SiteEngineer) Mo.8128947892

Please submit the offer in seal cover only after verification of work at site.

Time for site visit:-3.30 P.M. on date 09.02.2021

Subject mention on seal cover as under.

Name of work: - Repairing of Toilet Block (Stair case side LHS) in Adm.Bldg. At Dahej SEZ part-1

Address: - Office of Dahej SEZ Ltd.

Dahej SEZ Part-1,

At & Po:- Dahej,

Ta :- Vagra

Dist:- Bharuch

Last date of submission on or before 5:00PM on Date. 16.02.2021

Note:-1) Only Pre-qualified contractor of Dahej SEZ Ltd. Is eligible to quote / submit

2) Price bid- Agency has to quote the rate including all taxes but without (GST) as per SEZ Act &Rule and invoice is to be raised under GST Act and mentioned "supply to SEZ under LUT/Bond without payment of GST".

Name of work :- - Repairing of Toilet Block (Stair case side LHS) in Adm.Bldg. At Dahej SEZ part-1

Sr.No.	Description	Unit	Qty	Submitted rate	Submitted rate in Words(Rs.)	Total Amount (Rs.)
1	Providing and laying Glazed Tiles 8mm to 10mm thick 12" X 12" in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1-cement : 3-Coarse sand)finishing with flush pointing in white cement .ect complete as per requirement by DSL. (Brand and shade as approved by DSL)	Sq.Mtr	16.00			
2	Green marble repairing (Removing & Re-fixing existing green marble) Groove cutting in existing green marble, removing existing bed and re fitting with filling existing green marble required material & green colour including finishing upto satisfaction of DSL	Sq.Mtr	30.00			
3	Toilet Leakage repairing work Repairing of drainage line / Water Supply line in toilet at 1st floor including demolition, Pipe repairing, new pipe fitting, repairing of tile floor, tile fitting, etc. Complete as per instruction give by DSL time to time	JOB	1.00			
4	Providing and fixing single layer water proof gypsum board 12.5 mm thick of the make new good group co.ltd or equivalent. Company section using water proof board of size 1220mm x 1830mm x 8.0 mm suspended by G.I. suspender of size 25mm x 3mm x with intermediate channel of size 18mm x 40mm x .80mm at 1220 mm center to center ceiling section of size 40mm x 35mm x .55mm at 457mm c/c and perimeter channel A size 20mm x 27mm x 30mm x .50mm at edges & drops including paper tap sand soft cleat, anchor fastener, scotch bolt connecting cleant joining compound top coat on ceiling including making necessary opening for light fitting, diffuser etc. complete as per detail as directed	Sq.Mtr	100.00			
5	Color Work Providing and applying 3 coats of Plastic emulsion paints (as per approved by DSL) to walls / ceiling wich includes preparation of surface with Birla Putty. Rate to include for cleaning the existing surface with wire brush, applying primer, 2 coat of birla putty etc complete as directed by engineer in charge.	Sq.Mtr	100.00			
6	20watt LED tube light with fitting and surface holder plate and pin type addpter (crompton.syska,philips with one year guarantee)	No.	7.00			
7	Providing and laying polished green marble flooring over 20mm thick base of cement mortar 1:6 laid over & jointed with grey cement including rubbing and polishing etc.	Sq.Mtr	10.00			
				Total =		

Tender Amount Figure :

Word :

Sign & Stemp of Authority

- Note:-**
- 1) Please visit the site and submit the offer /Rate
 - 2) DSL reserve the right to increase / decrease scope of work / item/ Quantity as decided by DSL Authority.
 - 3) Rate to be quoted without TAX
 - 4) If agency fails to submit LUT then payment will process as per SEZ Act & Rule.

Place :-

Date :-